BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Construction of culverts in Bagalagunte in ward no. 14

Sl. No	Description of work	Unit	Qty	Rate Quoted by Sri. N.Thippeswamy	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & IWTD -SR 2016-17)	Cum	52.80	250.0	Rupees Two Hundred Fifty Only
2	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.3) PWD - SR 2016-17)	Cum	7.92	4950.0	Rupees Four Thousand Nine Hundred Fifty Only
3	KSRB 5.2.3 Providing and constructing granite/trap/basalt size stone masonry in foundation in cement motor 1:6, Stone hammered dressed in courses not less than 20 cms high. Bond stones at two m apart in each course including cost of materials, labour, curing including cost of materials, labour, curing complete as per specifications KBS 5.1.13 Page No 23/Item No 5.6/ PWD SR 2016-17	Cum	29.88	3650.0	Rupees Three Thousand Six Hundred Fifty Only
4	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 113/ Item No. 15.3 / PWD SR 2016-17	Sqm	28.80	85.0	Rupees Eighty Five Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications, Specification NO KBS 4.6.2 Page No 15/ Item No 4.31/PWD SR 2016-17	Sqm	24.00	350.0	Rupees Three Hundred Fifty Only
6	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC Cement @220 kgs with 20 mm and down size graded granite metal course aggregates @ 0.84 cum and fine aggregates @0.56 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well comated, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per , Specification NO KBS 4.1,4.2 Page No 13/ Item No 4.7/PWD SR 2016-17	Cum	2.16	6300.0	Rupees Six Thousand Three Hundred Only
7	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.6) PW, P & IWTD - SR 2016-17)	Cum	24.48	5300.0	Rupees Five Thousand Three Hundred Only
8	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. for TMT Bars Fe 500 Specification No.KBS 4.6.3 (Page No.17, Item No. 4.46.2) 2016-17	Tonnes	2.33	52000.0	Rupees Fifty Two Thousand Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 150 Item No. 17.1 PWD SR 2016-17	Cum	52.80	250.0	Rupees Two Hundred Fifty Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division